

Name of work: - Disconnect all the separate individual incoming line,  
 And accumulate all the connection into a common panel board  
 By providing underground cable at Siliguri College.

1	Supply, lying, testing of UG aluminum cable XLPE armored 1.1 KV grade 4 core 150 MM SQ partly underground and partly on wall with suitable clamp.	Mtr	100	
2	Supply, lying, testing of UG aluminum cable XLPE armored 1.1 KV grade 4 core 70 MM SQ partly underground and partly on wall with suitable clamp.	Mtr	225	
3	Supply, lying, testing of UG aluminum cable XLPE armored 1.1 KV grade 4 core 50 MM SQ partly underground and partly on wall with suitable clamp.	Mtr	55	
4	Supply, lying, testing of UG aluminum cable XLPE armored 1.1 KV grade 4 core 35 MM SQ partly underground and partly on wall with suitable clamp.	Mtr	295	
5	Earthing complete	No	2	1
6	Junction Box with bus bar 200 Amp	Set	1	3
	TOTAL			